



3540 SE 28th Avenue Portland, Oregon 97202

Office 503.234.2118  
Toll Free 877.234.2118  
Fax 503.331.7133

www.soilsolutionsenvironmental.com

## Construction Change Directive

Michael Green  
Woodland School District

Re: Yale Elementary School Heating Oil Tank Decommissions

Good afternoon,

In the process of removing two heating oil tanks at Yale Elementary School in Ariel, WA, Soil Solutions encountered heating oil contamination beneath the 1,000-gallon tank. In order to meet WA Department of Ecology guidelines, it is necessary to remove all heating oil contaminated soil with concentrations in excess of 2,000ppm of diesel. Soil Solutions will excavate petroleum-contaminated soil and place it in a drop box or dump truck for transport to the Hillsboro landfill. Excavation will continue until there are no longer visual and olfactory signs of soil contamination, or until time limits require the crew to leave the site (Deadline: 4pm Wednesday 7/3). Soil Solutions will collect post-excavation samples and submit them to an independent lab for analysis. Upon completion of excavation, Soil Solutions will backfill the excavation pit to surface grade with crushed rock in 2-ft lifts. Special compaction requirements or compaction testing are not included in this proposal. The cost of excavation, transport, disposal and backfill will be billed at a cost of **\$295/ton**, with a 12-ton per load minimum. This cost assumes that excavation is completed while onsite 7/2 and 7/3 and that re-mobilization to the site is not required. This proposal assumes that groundwater will not be encountered onsite. This proposal is in addition to all previous contracts regarding this project. Please sign and return contract as soon as possible as we are moving forward under your emailed authorization. If you have any questions please feel free to give me a call.

Regards,

Tess Chadil

Senior Project Manager

The above prices, specifications, and conditions are satisfactory and are hereby accepted. Soil Solutions is authorized to do the work as specified. Payment will be made as outlined below. I have read and received the "Information Notice to Owner about Construction Liens" and "Consumer Notification" sheets as provided by Soil Solutions.

Signature of Property Owner:  Date July 2, 2013

Print Name: Michael Z. Green

Payment in full is due within thirty (30) days of invoice date. A late charge of 1.5% monthly (18% APR) will be applied to all past due accounts. Any alteration or deviation from above specifications involving extra costs will be executed only upon written order and will become an extra charge over and above the agreed upon costs as noted above. All agreements are contingent upon strikes, accidents or delays beyond our control. Proposal is valid for 60 days.