

DATE: April 13, 2015

RE: Change Order No. 21

Board Summary

Project: New Woodland High School

Change Order 21 amount: \$37,436.00

• CCD 005 – This change is to compensate the contractor for excavating through the geogrid to install utilities that were within the grid near the building.

- CCD 099 There were open spaces under the treads at the stair near
 Administration. These openings which had access to the space behind the adjacent
 wall would be problematic in that debris (trash, banana peels, etc.) could be put in
 these holes. This change was to install gypsum board to the underside of the stair
 to close off these holes.
- CCD 112 This added galvanized uni-strut and concrete foundations to provide a place to mount an electrical panel near the baseball field.
- CCD 113 Provide power to the Aux. Gym indoor batting cage to raise and lower the nets. Not show on drawings.
- CCD 114 Provide, program, and install additional controls for the boiler circulation pump start/stop control and air fan in Boiler Room. Not shown on drawings.
- CCD 116 Provide wood trim around fire extinguishers and other items at the wood wall paneling. Not detailed or shown on drawings.
- CCD 117 Add additional coat of paint beyond what was specified to correct appearance problems on the west wall of the Commons.
- CCD 118 Change tiles at locker room shower floors for smaller tiles to improve traction and safety in showers.
- COP 062 Provide metal inserts in floor electrical boxes at Shared Activity Area.
 Floor boxes were specified incorrectly and did not sit flush and caused a tripping hazard.

CSG Office Locations

ESD 112 2500 NE 65th Avenue Vancouver WA 98661 P 360.750.7500 F 360.750.9706

ESD 101 4202 S Regal Street Spokane WA 99223 P 509.789.3800 F 509.456.2999

ESD 123 3918 W Court Stree Pasco WA 99301 P 509.547.8441 F 509.544.5795

ESD 171 430 Olds Station Road Wenatchee WA 98801 P 509.665.2610 F 509.662.9027 NW ESD 189

1601 R Avenue Anacortes WA 98221 P 360.299.4000 F 360.299.4070



Specialists in School Buildings

- COP 063 Provide metal flashing at the top of concrete block walls at the grandstand. No flashing shown on drawings.
- COR 172 Provide steel angles at the floor seismic joint to hold the joint cover. No support shown on drawings.
- COR 276 Provide power to the multi-station hand washing sink at CTE shop. The sink has a hands free electronic start and requires power. Power not shown on drawings.
- COR 293 Provide tackable wall surface to the hallway entrance to the library.
 Tackable surface was requested by the staff and the original solution was to provide premade tack boards. Electrical outlets conflicted with the premade tack boards so a field applied tackable surface, similar to elsewhere in the building, was installed.
- COR 303 Revise game line painting on the gym floor.
- COR 312 Provide additional HVAC duct dampers to provide access to control actuators. Original dampers were not accessible.

End