



June 8, 2020

Blue1 Energy Equipment - Sourcewell Contract 040215-PGE

Mr. Shannon Barnett
KWRL Transportation Director
Woodland School District
800 2nd St.
Woodland, WA 98674-0400

We are pleased to quote you the following fuel system installation and UST removal proposal available through our Sourcewell contract #040215-PGE. Two 12,000 Gallon UL-2085 Tank Systems previously purchased on PO 1309000170 on June 28, 2019 to be installed. Scope and installation based on Maul Fauster Alongi engineered drawings KWRL Diesel Tank Replacement, KWRL Transportation Cooperative.

Phase 1 Scope of Work:

- Mobilize to site and secure work area with temporary fence.
- Layout for demo and provide private locates for new and existing tank work.
- Remove existing fence and install new as per plan.
- Saw cut, demo and remove existing asphalt as per plan.
- Excavate for new tank slab, drive slab, oil water separator (OWS) catch basin (CB) and trenching for OWS outlet piping.
- Excavate for new electrical, provide and install underground conduit.
- Supply and install new CB, OWS, emergency shut of valve and piping to SSWR manhole.
- Coordinate for any required inspections.
- Backfill and compact.
- Supply place and compact 8" crushed rock for tank slab and drive slab base.
- Excavate for concrete pad at fire hydrant.
- Turn existing fire hydrant 180 degrees.
- Supply rebar and form tank slab, drive slab and hydrant slab as per plans.
- Supply and place all bollards.
- Supply place and finish concrete.
- Set and anchor owner supplied tank after concrete has sufficiently cured.
- Supply and install new canopy structure.
- Assemble owner supplied tank equipment and piping.
- Install owner supplied dispenser stand and dispenser.
- Provide and install remainder of electrical.
- Provide and place asphalt patch around tank slab electrical trench and OWS piping trench.
- Start up and calibrate dispensers.



Phase 2 Scope of Work:

- One call utility notification and private locates.
- Mobilization of personnel and equipment
- Provide 6 foot security fencing around tank nest and provide portable toilet for site workers
- Sawcut piping trench from dispensers to UST slab
- Remove canopy, dispenser island, footings and drive slab concrete, offsite disposal of all
- Remove concrete and asphalt over piping trench, remove UST tank slab, load, transport and dispose of off site
- Flush and rinse product piping and UST's, transport and dispose of at approved disposal facility (assume 3" or less in each tank)
- Remove piping, dispose of offsite.
- Excavate overburden from above and around UST's to allow for tank removal, transport and dispose of overburden offsite as " Non Contaminated, unsuitable fill material"
- Remove (3) 6000-gallon and (1) 7000-gallon single wall steel UST's
- Cut, clean, load and transport UST's to offsite recycling facility
- Provide Site Assessor for soil sampling collection as needed.
- Import, place, backfill and compact backfill material. Blue1 assumes that pea gravel or sand will be required as backfill to get backfill to level above water table, capping excavated area with imported structural fill material (1-1 ½" minus)
- Repave drive slab and piping trench from dispenser area to tank nest with 4" asphalt, including tack coat at joints
- Clean site and demobilize.

Notes:

- All permitting by others.
- All equipment and piping to be provided by owner and assembled by PNE.
- Assume canopy footings up to 5'x5'x8'.
- Painting of canopy columns and bollards included.
- Required fire extinguisher included.



Exclusions:

- Washington State Sale Tax.
- Landscape and seeding.
- Engineering except for canopy structure and footings.
- 3rd party inspections
- Dewatering
- Bonding & Builders risk insurance

Pricing Summary:

<u>Sourcewell Part Number</u>	<u>Description</u>	<u>Sourcewell Price</u>
EZ-HRS	Phase 1 AST Installation	\$364,490.00
EZ-HRS	Phase 2 UST Removal	\$96,373.00
EZ-Storage	7 Months @ \$350/ mo	\$2,450.00
EZ-FRT	Estimated Freight for Two Tanks	\$4,300.00
Sourcewell Total		\$467,613.00

Standard Blue1 Energy Equipment-Sourcewell terms and conditions apply. Pricing does not include any applicable sales tax. Any applicable sales tax and freight will be added to final invoice. Estimated freight subject to change/fuel surcharge.

**Puregreen Equipment Services
DBA/Blue1 Energy Equipment**

Woodland School District - KWRL

Printed Name

Printed Name

Signature

Signature

Title

Date

Title

Date